

Grundy County Demolition of Residential Structure Specifications

Addendum # 01

A bidder raised the following questions regarding the specifications:

1). Are driveways to be removed to the Right of Way?

Direction: Driveways should be removed to the edge of right of way.

2) Should concrete foundation footings be completely removed or only to four feet below finish grade?

Direction: Foundation footings and basement walls less than four feet in depth should be removed.